



March 10, 2014

CITY OF RANCHO MIRAGE ADDENDUM NO. 2

BOB HOPE DRIVE (CP 12-276) AND FRANK SINATRA DRIVE (CP 12-278) MEDIAN ISLAND LANDSCAPE REHABILITATION PROJECT

TO ALL PROSPECTIVE BIDDERS:

The following changes, corrections, and clarifications shall be made a part of the plans, specifications, and contract documents on this project:

1. Both Bob Hope Dr. and Frank Sinatra Dr.:

- a. Repairs of existing stamped concrete** - Line item #8 on the Bid Proposal sheets that references Ackerstone pavers is to be used for repairs of existing stamped concrete, with the following requirements:
 - 1. Sections of existing stamped concrete that are damaged, or have been lifted by a height of ¼" or more, are to be repaired.
 - 2. Repair these sections by sawcutting the damaged section to the point where the stamped concrete is level with the top of curb.
 - 3. Ackerstone pavers (and associated material) are to be used for these repairs.
- b. Quick couplers** - A quick-coupler should be installed every 150 ft.
- c. Robusta palms to be removed by others** - the Robusta palms will be removed by others prior to project construction. However, the holes will not be backfilled at that point. That work will be part of the new construction as a part of this landscape project. Please refer to Demolition Note #10 on page L-1.0 regarding the dispersing of soil.
- d. Power washing and sealant** - Both new pavers and existing stamped concrete are to be power washed and sealed. Refer to the project specifications and Addendum #1 that discuss sealing.
- e. Valves** - Valves that appear throughout the plans for both Bob Hope Dr. and Frank Sinatra Dr. should be Rainbird PEB valves. Installation details are defined in Detail C "Automatic Valve" on Pg. L-4.00 of the Frank Sinatra Dr. plans.

2. Frank Sinatra Dr.:

- a. The plans currently call to reuse the existing electrical conduit. This is not correct. All electrical conduit shall be new, and mainline shall be 1.5" conduit.

3. Bob Hope Dr.:

- a. **Eisenhower Hospital's north entrance** – Contractor shall protect in place the newer landscape material that was installed on the south side of Eisenhower Hospital's north entrance (from station 26+26 to approximately 27+18). This covers the area from the nose head to approximately 92 ft. southward. Bidders shall prepare their bids based on the adjustments identified above.

All other project plans and specifications stay the same.

ALL BIDDERS SHALL ACKNOWLEDGE RECEIPT OF THIS ADDENDUM NO. 2 AND ITS ATTACHMENTS BY SIGNING THE ATTACHED RECEIPT SHEET AND SUBMITTING THE SIGNED SHEET WITH THEIR BID PROPOSAL. FAILURE TO COMPLY MAY BE CAUSE TO CONSIDER THE BID NON-RESPONSIVE.

Sincerely,



Randy Viegas
Project Manager

ADDENDUM RECEIPT SHEET

ADDENDUM NO. 2

**TO: CITY OF RANCHO MIRAGE
DEPARTMENT OF PUBLIC WORKS**

RE: CP 12-276 and CP 12-278

Receipt of Addendum No. 2 is hereby acknowledged.

Bidder

Signature

Date

**THIS PAGE TO BE ATTACHED TO YOUR BID.
FAILURE TO ATTACH THIS PAGE TO YOUR BID MAY BE
CAUSE TO CONSIDER YOUR BID NON-RESPONSIVE.**