


CITY OF RANCHO MIRAGE



August 31, 2016

**CITY OF RANCHO MIRAGE
ADDENDUM NO. 1**

**Rancho Mirage Community Park Storm Drain
PROJECT NO. C.P. 16-322**

TO ALL PROSPECTIVE BIDDERS:

The following changes, corrections, and clarifications shall be made a part of the plans, specifications, and contract documents on this project:

Questions asked by Bidders during advertisement period and City Responses.

Question 1) What is the required bedding detail for the 18" HDPE piping and fittings?

Answer 1) HDPE Pipe bedding and backfill requirements shall conform to the manufacturer's installation guidelines. Alternatively, Pipe Bedding and Backfill material may be obtained from trench excavation and should be clean and free from objectionable material, exhibiting a sand equivalent (SE) value of 20 or greater. All native earth backfill shall be placed in lifts no greater than approximately 6 inches in thickness, watered or air-dried as necessary to achieve near optimum moisture conditions, and then mechanically compacted in place to a minimum relative compaction of at least 90%.

*****END ADDENDUM NO. 1*****

All other project plans and specifications shall remain the same.

ALL BIDDERS SHALL ACKNOWLEDGE RECEIPT OF THIS ADDENDUM NO. 1 AND ITS ATTACHMENTS BY SIGNING THE ATTACHED RECEIPT SHEET AND SUBMITTING THE SIGNED SHEET WITH THEIR BID PROPOSAL. FAILURE TO COMPLY MAY BE CAUSE TO CONSIDER THE BID NON-RESPONSIVE.

Sincerely,

for William A. Enos
William A. Enos
City Engineer

ADDENDUM RECEIPT SHEET

ADDENDUM NO. 1

TO: CITY OF RANCHO MIRAGE
CITY ENGINEER

RE: CITY PROJECT NO. 16-322

Receipt of Addendum No. 1 and its attachments is hereby acknowledged.

Bidder

Signature

Date

**THIS PAGE TO BE ATTACHED TO YOUR BID.
FAILURE TO ATTACH THIS PAGE TO YOUR BID MAY BE
CAUSE TO CONSIDER YOUR BID NON-RESPONSIVE.**